

# South Carolina Regional Transmission Planning

## Stakeholder Meeting

Hilton Garden Inn

North Charleston, SC

September 12, 2014

## Purpose and Goals of Today's Meeting

- FERC Order 1000 Update
- Review and Discuss Modifications to Transmission Expansion Plans
- Review and Discuss Assessment and Planning Studies
  - CTCA
  - ERAG
  - SERC
  - Other
- EIPC Stakeholder Group Activities

# FERC Order 1000 Transmission Planning and Cost Allocation

Clay Young

# FERC Order 1000

- Planning Requirements (Regional and Interregional)
  - Reliability
  - Economics
  - Public Policy
- Cost Allocation Requirements
- Non-incumbent Developer Requirements

# Order 1000 Update



- **Regional - Milestones**
  - July 21, 2011 FERC issued Order 1000
  - Oct. 11, 2012 SCE&G filed a revised Attachment K (v1) including proposed Order 1000 Regional Processes
  - April 18, 2013 FERC issued Order Accepting SCE&G filing but requiring revisions
  - Oct. 15, 2013 SCE&G filed a revised Attachment K (v2) including proposed revisions

# Order 1000 Update



- (Continued) Regional – Milestones
  - May 14, 2014 FERC issued Order accepting SCE&G filing but requiring additional revisions
  - July 14, 2014 SCE&G filed a revised Attachment K (v3) including proposed additional revisions
  - FERC is reviewing
  - FERC established an Effective Date of April 19, 2013

# Order 1000 Update



- **Interregional - Milestones**
  - July 10, 2013 SCE&G filed a revised Attachment K including proposed Order 1000 Interregional Processes
  - FERC is reviewing

## Appendix K-3 Timeline for Local Transmission Planning

**Economic & Rel.  
( Local )**

**Meeting 1 – Oct/Nov/Dec**

Stakeholder input into the study processes; provide key assumptions

SCE&G presents the Local Transmission Plan

**Meeting 2 – Jan/Feb/Mar**

Stakeholders ID and request economic sensitivities to be studied

**Meeting 3 – April/May/June**

SCE&G reviews initial and final RTP study results; review regional and interregional reliability studies

SCE&G presents additions or changes to the Local Transmission Plan

**Meeting 4 – July/Aug/Sept**

Review and discuss results of economic studies

Model building

Analysis of studies by SCE&G

**Public Policy  
( Local )**

**Meeting 1 – Oct/Nov/Dec**

SCE&G announces transmission needs driven by public policy requirements for which solutions will be evaluated.

**Meeting 2 – Jan/Feb/Mar**

Local projects **for Public Policy Requirements** must be submitted by January 15.

SCE&G and Stakeholders may discuss proposed projects.

**Meeting 3 – April/May/June**

Stakeholders may comment on any proposed projects.

**Meeting 4 – Jul/Aug/Sept**

Stakeholder comments discussed at meeting.

Stakeholders review proposals

SCE&G review proposals and stakeholder comment.

**Meeting 5 – Oct/Nov/Dec**

No scheduled activities

**Meeting 6 – Jan/Feb/Mar**

SCE&G announce any solutions for Public Policy Requirements

**Meeting 7 – April/May/June**

No scheduled activities


**Meeting 8 – July/Aug/Sept**

Stakeholders propose transmission needs driven by public policy requirements by July 15.

SCE&G evaluates proposed transmission needs driven by public policy requirements



**Appendix K-4  
Timeline for Regional Transmission Planning**



# FERC Order 1000

## Stakeholder Input, Comments and Questions


# Proposed Transmission Expansion Plan Changes

SCE&G

Jeff Neal

- These projects represent the current transmission plans within the SCRTP footprint
- The expansion plan is continuously reviewed and may change due to changes in key data and assumptions
- This presentation does not represent a commitment to build

# SCE&G Planned Projects



## SCE&G Current Projects

- **NND Related Projects**
  - VCS2 – Lake Murray 230kV #1
  - Denny Terrace – Lyles 230/115kV Rebuild
  - Saluda River Transmission 230/115 kV Substation
  - St. George 230kV Substation
- **TPL/Reliability Based Projects**
  - Lake Murray – SRT – Lyles 230/115kV
  - Hagood – Bee Street 115kV Rebuild
  - Hagood – Faber Place 115kV Rebuild
  - Yemassee – Burton 115kV #2 Rebuild


## VCS2 – Lake Murray 230 kV #1

- Construct 230 kV SPDC B1272 ACSR conductor, approximately 24 miles from VCS2 to Lake Murray
  - SPDC construction to include new VCS2 – St. George 230 kV #1
- Add new 230 kV terminal at Lake Murray
- Scheduled to be completed by September 30, 2014
  - Initially scheduled for completion in May, 2014. Delayed due to outage constraints and DOT permitting for I-26 crossing

# VCS2 – Lake Murray 230 kV #1

VCS2

Lake Murray






## Denny Terrace – Lyles 230/115 kV Rebuild

- Tear out existing lattice tower construction, rebuild 230 kV SPDC B1272 ACSR conductor, approximately 2.6 miles
  - SPDC construction to include:
    - Denny Terrace – Lyles 230 kV (NND)
    - Denny Terrace – Lyles 115 kV #1 ([NERC TPL System Improvement](#))
- Upgrade 230 & 115 kV terminals at Denny Terrace and Lyles
- Scheduled for completion by January 30, 2015
  - Initially scheduled for completion in Fall 2013, delayed due to outage constraints and other issues. Outage constraints alleviated with completion of two VCS2 – Lake Murray 230 kV circuits.


# Denny Terrace - Lyles 230/115 kV Rebuild



Denny Terrace

Lyles


# Saluda River Transmission 230/115 kV




- Construct 230/115 kV substation at Saluda River
  - One 230/115 kV 336 MVA Autotransformer
  - Four 230 kV line terminals
  - Four 115 kV line terminals
- Lake Murray – Lyles 230 kV construction and fold-in added to project after decision to retire McMeekin ([NERC TPL System Improvement](#))
- Lyles – SRT to be completed by 5/31/15, SRT – Lake Murray to be completed by 5/31/16 (tentative) ([NERC TPL System Improvement](#))

# Saluda River Transmission 230/115 kV

V.C. Summer



# Saluda River Transmission 230/115 kV




Saluda River Transmission  
230/115 kV

VCS2 - St. George #1&#2  
230 kV

Lake Murray – SRT 230 kV  
&  
Lake Murray – SRT 115 kV


SRT – Lyles 230 kV  
&  
SRT - Lyles 115 kV

# St. George 230 kV Switching Station




- Construct 230 kV substation at St. George
  - Seven 230 kV line terminals
  - Back to Back bus tie breaker
- Scheduled for completion May 2016, with surrounding line rebuilds completed by May 2017

# St. George 230 kV Switching Station



# St. George 230 kV Switching Station




Summerville



## Hagood – Bee Street 115 kV Rebuild

- Rebuild existing 115 kV line between Hagood – Bee Street, upgrading from 795 ACSR to B795 ACSR.
- Project required to alleviate N-2 contingency in combination with full Hagood ICT's output, and improved reliability of steel pole construction
- Scheduled for completion by December 31, 2015

# Hagood – Bee Street 115 kV Rebuild




Hagood – Bee Street 115 kV  
795 ACSR

- Loss of Church Creek – St. Andrews 115 kV & Hagood – Charlotte St. 115 kV
- Full Hagood output

## Hagood – Faber Place 115 kV Rebuild

- Rebuild existing 115 kV line between Hagood – Faber Place, upgrading from 795 ACSR to 1272 ACSR.
- Project required to alleviate N-2 contingency in combination with Hagood generators offline, and improved reliability of steel pole construction
- Hagood – Faber Place 115 kV #2 to be built in 2017 to further alleviate loading constraints, and to provide increased reliability to peninsula
- Scheduled for completion by May 31, 2015

# Hagood – Faber Place 115 kV Rebuild



Hagood – Faber Place 115 kV  
795 ACSR


- Loss of Church Creek – St. Andrews 115 kV & Charlotte St. – Faber Place 115 kV
- No Hagood Generation

## Yemassee – Burton 115 kV #2 Rebuild

- Remove existing H-Frame 477 ACSR 115 kV line, rebuild approximately 21 miles SPDC B795 ACSR
  - Yemassee – Burton 115 kV #2 upgraded
  - Yemassee – Burton 115 kV #3 created
- Upgrade/Add 115 kV terminals at Yemassee
- Project required to alleviate N-2 contingency overload that requires load shedding under peak conditions
  - Radial load shed only, does not have any adverse effects on BES
- Scheduled for completion by December 31, 2015


Yemassee

# Yemassee - Burton 115 kV Rebuild



Burton


# Yemassee – Burton 115 kV #2 Rebuild



Current Configuration:

- 1-230 kV 1272 ACSR
- 2-115 kV 477 ACSR

Total Capacity: **500 MVA**



Future Configuration:

- 1-230 kV 1272 ACSR
- 1-115 kV 477 ACSR
- 2-115 kV B795 ACSR

Total Capacity: **1,074 MVA**

# SCE&G Planned Project Scope/Date Changes

## Bayview-Charlotte St 115 kV #2 Underground Cable Construct

- Damage to conduit discovered shortly after initial installation/energization, complete and extensive project overhaul required
- Completion delayed to **May 31, 2015**



# SCE&G Planned Project Scope/Date Changes

## Urquhart – Graniteville 230/115 kV Rebuild SPDC

- Numerous delays encountered, including R/W issues, underbuild, etc.
- Currently exploring other options to replace this project
- Scheduled for completion in **May 31, 2016** but most likely will be delayed

# SCE&G Planned Project Scope/Date Changes

## Cainhoy - Hamlin/Mt. Pleasant 115 kV Rebuild as Double Circuit

- This area is winter peaking and it was determined that the project is needed prior to 2017 winter
- Expedited date to **12/01/2016**

# SCE&G Planned Project Scope/Date Changes

## Queensboro 115 kV Switching Station Construct

- This project was previously scheduled with an in service date of 05/31/2019
- Project expedited to **12/01/2016** to address system limits in the West Ashley/James Island area
- Also studying possible SCPSA tie-line to serve as back-up support for SCE&G and SCPSA under emergency conditions

Questions?

# Proposed Transmission Expansion Plan Changes

Santee Cooper

Rick Thornton

# Transmission Network Completed Projects

- Winnsboro 230-69 kV Substation 05/2014
- VCS-Winnsboro 230 kV Line 05/2014
- Bucksville 230-115 kV Substation 05/2014
- VCS-Pomaria #2 230 kV Line 06/2014

# Transmission Network

## Active Projects


- Richburg 230-69 kV Substation 03/2015
- Winnsboro-Richburg 230 kV Line 04/2015
- Purrysburg 230-115 kV Substation 06/2015
- Purrysburg-McIntosh 230 kV Line #2 06/2015
- Winyah-Bucksville 230 kV Line 12/2015

# Transmission Network


## Active Projects

- Richburg-Flat Creek 230 kV Line 06/2016
- Bucksville-Garden City 115 kV Line 06/2016
- Sandy Run 230-115 kV Substation 05/2017
- Pomaria-Sandy Run 230 kV Line 05/2017
- Sandy Run-Orangeburg 230 kV Line 11/2017






## Bucksville Transmission Projects



# Purrysburg 230-115 kV Substation




# Pomaria-Sandy Run-Orangeburg 230 kV Line

Pomaria  
230-69 kV  
Substation

Sandy Run  
230-115 kV  
Substation


Orangeburg  
230-115-69 kV  
Substation




# Transmission Network Planned Projects


- Bucksville-Myrtle Beach 115 kV Line 12/2016
- SCE&G Queensboro-SCPSA Johns Island  
115 kV Interconnection 06/2017
- Marion-Red Bluff 230 kV Line 12/2018
- Dalzell-Lake City 230 kV Line 04/2020
- Sandy Run-Pinewood 230 kV Line 12/2021

## Bucksville – Myrtle Beach 115 kV Line




## SCE&G Queensboro – SCPSA Johns Island 115 kV Interconnection






## Marion-Red Bluff 230 kV Line






## Dalzell-Lake City 230 kV Line



## Sandy Run-Pinewood 230 kV Line



# Proposed Transmission Expansion Plan Changes

## Stakeholder Input, Comments and Questions


# Reliability Assessment Studies

Rick Thornton

# Multi-Party Assessments

- Carolina Transmission Coordination Arrangement (CTCA) Assessments
- Southeastern Electric Reliability Corporation (SERC) Assessments
- Southeast Inter-Regional Participation Process (SIRPP)

# CTCA Future Year Assessments



## CTCA Purpose

- Collection of agreements developed concurrently by the Principals, Planning Representatives, and Operating Representatives of multiple two-party Interchange Agreements
- Establishes a forum for coordinating certain transmission planning and assessment and operating activities among the specific parties associated with the CTCA

# CTCA Purpose

## Interchange Agreements associated with the CTCA

Duke Energy Carolinas (“Duke”) and Duke Energy Progress (“Progress”)

Duke Energy Carolinas (“Duke”) and South Carolina Electric & Gas Company (“SCE&G”)

Duke Energy Carolinas (“Duke”) and South Carolina Public Service Authority (“SCPSA”)

Duke Energy Progress (“Progress”) and South Carolina Electric & Gas Company (“SCE&G”)

Duke Energy Progress (“Progress”) and South Carolina Public Service Authority (“SCPSA”)

South Carolina Electric & Gas Company (“SCE&G”) and South Carolina Public Service Authority (“SCPSA”)



# CTCA Power Flow Study Group

- Duke Energy Carolinas (“Duke”)
- Duke Energy Progress (“Progress”)
- South Carolina Electric & Gas (“SCEG”)
- South Carolina Public Service Authority (“SCPSA”)

# CTCA Studies


- Assess the existing transmission expansion plans of Duke, Progress, SCEG, and SCPSA to ensure that the plans are simultaneously feasible.
- Identify any potential joint solutions that are more efficient or cost-effective than individual company plans, which also improve the simultaneous feasibility of the Participant companies' transmission expansion plans.
- The Power Flow Study Group ("PFSG") will perform the technical analysis outlined in this study scope under the guidance and direction of the Planning Committee ("PC").

# CTCA Studies 2014 Study

- LTSG 2014 Series 2018 Summer and 2021 Summer Peak Load Models
- PFSG analyzed existing transmission expansion plans using NERC and individual companies' reliability criteria
- Determine if there are opportunities for joint alternative plans
- Final report released later this year

# SERC LTSG Assessments

## SERC Future Year Assessments Long Term Study Group (LTSG)



# SERC LTSG Study Purpose

- Analyze the performance of the members' transmission systems and identify limits to power transfers occurring non-simultaneously among the SERC members.
- Evaluate the performance of bulk power supply facilities under both normal and contingency conditions for future years.
- Focus on the evaluation of sub-regional and company-to-company transfer capability.

# SERC Long Term Study Group 2014 Work Schedule

- LTSG Data Bank Update –May 20-22 Hosted by TVA
- Study Case: 2016 Summer Peak Load
- Work completed by LTSG August thru October
- Report issued late November 2014.

# SERC Assessments

Questions?



# SIRPP Assessments

# SIRPP

## 2013/14 Economic Sensitivity Study

- 2015, 2016, and 2018 Summer Peak Models evaluated
- Each study participant provided updated internal model data
- Scenarios Evaluated
  - Shelby 500 kV (HVDC) to TVA/Southern 3,500 MW
  - Sullivan 765 kV (HVDC) to PJM/VACAR 3,500 MW
  - TVA to LG&E/KU 700 MW
  - Duke to Santee Cooper 500 MW
  - SOCO to FRCC 500 MW

# SIRPP

## 2013/14 Economic Sensitivity Study

- Final Report Issued August, 2014
  - No SCE&G Facilities Impacted
  - No Santee Cooper Facilities Impacted

# SIRPP Assessments

Questions?

# Eastern Interconnection Planning Collaborative Update

Phil Kleckley

## About the EIPC

- 22 Planning Authority (Planning Coordinator) members including ISOs/RTOs, non-ISO regions, municipals, cooperatives, ...
- Members are from the U.S. and Canada
- Approximately 95% of the Eastern Interconnection customers covered

## EIPC Supporting Activities

- CEII: Continue to make EIPC models available to those who have completed the EIPC CEII process (based on regional clearance)
- Website: [www.eipconline.com](http://www.eipconline.com)
  - Continue to host the EIPC website
  - Review current EIPC website and recommend modifications as appropriate
  - Post material from both grant and non-grant EIPC activities

## EIPC Stakeholder Process

- Existing stakeholder groups previously created for other purposes such as compliance with FERC Order 890 will be used to facilitate stakeholder input
- Ensure a regional focus:
  - Present roll-up models and results
  - Receive stakeholder feedback, input, comments and suggestions on specific scenarios to be studied
  - Present the results of scenario studies
  - Seek stakeholder feedback on reports that are created



## EIPC 2013 Effort

- 2018 and 2023 summer peak models created
  - Model assembled utilizing most up to date information
- Steady-state load-flow model analysis performed
  - Transmission “Gap” Analysis
  - Linear Transfer Analysis
- Report assembled and posted to EIPC website  
[http://www.eipconline.com/Non-DOE\\_Documents.html](http://www.eipconline.com/Non-DOE_Documents.html)

## EIPC 2014 Study

- Webinar conducted March 25, 2014
- Presented study scenario options to stakeholders
  - 2 EIPC Proposals
  - 5 Stakeholder Proposals

# EIPC Study Selections (Stakeholder Suggested)

## Scenario A

2023 Summer Peak Load With Updated NY Transmission Owners' Transmission Solutions (and solicit other Regions' updates)

- Re-perform transfer analysis to identify effect of model updates on transfer capability between areas

## Scenario B

2023 Scenario A updates plus Heat Wave And Drought Conditions With Long Distance Transfers

- Perform Heat Wave and Drought Analysis

## EIPC 2014 Study

- Webinar conducted September 9, 2014
- Presented transfer analysis results of updated 2023 Summer Roll-up case
- Presented final input assumptions for Heat Wave & Drought scenario

# EIPC 2014 Study

## Transfer Analysis Results

- Analyzed 5,000 MW transfers between selected areas
- Monitored N-0 & N-1 branch overloads
- Updates to 2023 Roll-up showed no significant impact on Eastern Interconnection transfer capability



Source	Sink		Previous		New	
			FCITC (MW)	Lim. PA	FCITC (MW)	Lim. PA
FRCC	E	SERC	1600	DEF	1700	DEF
MISO	C	NPCC	3400	PENELEC-PJM	3100	PENELEC-PJM
MISO	D	PJM	>5000	N/A	>5000	N/A
MISO	E	SERC	>5000	N/A	>5000	N/A
MISO	F	SPP	650	EES	650	EES
NPCC	B	MISO	1800	NYISO	1350	NYISO
NPCC	D	PJM	1500	NYISO	1150	NYISO
PJM	B	MISO	1600	ALTW-MISO	1650	ALTW-MISO
PJM	C	NPCC	2100	PENELEC-PJM	2750	NYISO
PJM	E	SERC	>5000	N/A	>5000	N/A
SERC	A	FRCC	1900	SBA/FRCC	1900	SBA/FRCC
SERC	B	MISO	>5000	N/A	>5000	N/A
SERC	D	PJM	1900	BREC-MISO	4800	DVP-PJM
SERC	F	SPP	550	SWPA-SPP	500	SWPA-SPP
SPP	B	MISO	850	WERE-SPP	800	WERE-SPP
SPP	E	SERC	950	WERE-SPP	950	WERE-SPP

# EIPC 2014 Study

## Heat Wave and Drought Scenario Assumptions

- Submitted by: Eastern Interconnection States' Planning Council (EISPC)
- Model a severe and pervasive heat wave and drought condition in study year 2023
- Determine constraints if large amounts of power are transferred during extremely high temperatures and drought conditions

## EIPC 2014 Study

### Heat Wave and Drought Scenario Assumptions

- Utilize updated 2023 summer peak roll-up model
- Model effect of heat wave on sink area  
(scale up load by 5% or 15,000 MW)
- Model effect of drought condition on sink area  
(scale sink generation down by 5% - unused capacity not available)
- Model effect of power transfer from source  
(scale available generation up 30,000 MW)



# EIPC 2014 Study

## Heat Wave and Drought Scenario

- Perform N-1 contingency analysis on 200 kV and above and where lower voltage levels are required
- Monitor all lines 161 kV and above
- Use MUST transfer analysis to identify facilities with  $>3\%$  Transfer Distribution Factor

## 2014 Scenario Analysis Timeline

- 9/19/2014 Update 2023 Study Case for Heat Wave & Drought Scenario
- 9/30/2014 Complete Heat Wave & Drought analysis
- 10/31/2014 Produce draft report for 2023 Summer Roll-up case transfer analysis and Heat Wave & Drought Analysis
- 11/??/2014 Web Conference to present draft report to stakeholders – week of Nov. 17th

## 2014 Scenario Analysis Timeline

- 12/5/2014 Receive stakeholder written comments on draft report
- 12/??/2014 Possible interconnection-wide stakeholder meeting to review study report

Questions?

Contact Phil Kleckley

[pkleckley@scana.com](mailto:pkleckley@scana.com)

## Next SCRTP Meeting

- Update on FERC Order 1000
- Elect Voting Members
- Review and discuss Key Data and Assumptions for the next Planning Cycle
- Update on Transmission Expansion Plans
- SCRTP Email Distribution List will be notified
- Register online

# South Carolina Regional Transmission Planning

## Stakeholder Meeting

Hilton Garden Inn

North Charleston, SC

September 12, 2014